Abstract estimate of restoring Munimaduga Anicut below Byrasagara Tank, Chikballapur Taluk.

Sl. No.	Items of work	Per	Rate	Quantity	Cost
			Rs. a. p.		
1	Earthwork excavating foundations for masonry and stone work in clay and sandy soil.	C.yds.		488	
	Do in chettu soil ...	,,		14	
	Do in hard rock mixed with soft rock.	,,		54	
2	Dismantling brick masonry	C.ft.		71	
3	Burnt brick in surki mortar	,,		3,983	
4	Concrete in surki mortar	,,		181	
5	Burnt stone slabs 6″ thick	S.ft.		798	
6	Cut stone work	C.ft.		6	
7	Cutting grooves in slabs 2½″ × 2″ ..	R.ft.		11	
8	Providing teakwood shutter 1½″ thick including iron works locking arrangements, etc., complete.	S.ft.		9	
9	Removing old unsized coping slabs ...	,,		81	
10	Plastering with surki mortar	S.yd.		9·54	
11	Providing joggles for coping slabs of body and toe walls.	No.		60	
12	Burnt stone revetments apron work including jelly packing.	C.yds.		475	
13	Removings resetting oldstone work ...	,,		23	
14	Earthwork filling in behind wirywall and revetment.	,,	Lumpsum		
15	Earthwork cutting high ground in front of anicut to keep the full length of anicut in action.	,,		792	
16	Bond stones to secure proper bond with new and old wall.	S.ft.		27	
17	Baling water	...	Lumpsum		
	Total ...	...	...	...	...
	Contingencies at 5 % ...	...	...	...	...
	Grand Total ...	...	...	...	...

N. LAKSHMINARASIMHAIYA,
Executive Engineer.

SHIMOGA DIVISION.

Abstract Notification dated 3rd October 1928.

The attention of the public is invited to the notice of calling for tenders for restoring Kunitappa-Doddakere Tank, Reg. No. 121 of Sorab Taluk, *vide* pages 1105 to 1107 of the *Mysore Gazette* dated 11th October 1928.

M. A. SRINIVASACHARI,
Executive Engineer.

CHITALDRUG DIVISION.

Notice dated 19th September 1928.

Notice is hereby given that the sealed tenders will be received at the Office of the Executive Engineer, Chitaldrug Division, up to 26th November 1928, for constructing an additional Block to the Travellers' Bungalow at Chitaldrug. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1929.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chitaldrug between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of rupees 250 in cash or currency notes, as earnest money and be superscribed "Tender for constructing an additional Block to the Travellers' Bungalow at Chitaldrug," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract showing quantities for constructing an additional Block to the Travellers' Bungalow at Chitaldrug.

No.	Details of work	Per	Quantity
1	Dismantling the existing Mangalore Tiled roof and stacking ...	Sq.	6·10
2	Removing wood work and stacking	L. S.	...
3	Dismantling masonry walls and pillars, etc.	Cft.	637
4	Earthwork excavation foundation and filling basement ...	Cyd.	84
5	Concrete in chunam foundation	Cft.	821
6	Stone in mud foundation	,,	1714
7	Burnt brick in mud, basement and superstructure	,,	2437
8	Pillars of wire cut bricks in mortar including cement pointing and base and capital complete.	No.	14
9	Fixing old windows	Sft.	60
10	Fixing old lintel slabs	,,	85
11	Burnt stone slabs new dressed and fixed	,,	348
12	Pointing in mortar in basement	Sqr.	3·25
13	Stonecorbels dressed and fixed	No.	5
14	Teakwood wrought and put up with wood oiling	Cft.	155
15	Pukka terrace 9" thick complete	Sqr.	11·08
16	Parapet wall ornamental 2 high	Rft.	245
17	Teakwood eave boards ornamental 9" x 1"	,,	81
18	Cornice 9" allround	,,	197
19	Joining old and new masonry and tiled and terraced roof in verandah and other sundry works.	L. S.	...
20	Burnt brick in mortar	Cft.	162
21	Rolled steel girders including silicate blue paint, etc., complete ...	Cwt.	31
22	Teakwood panelled door with frames, hinges, clamps, iron fittings, etc., complete.	Sft.	233
23	Teakwood windows with frame and shutter on one side with half panelled at bottom and half glazed at top, including $\frac{3}{4}$" iron bars fixtures, etc., complete.	,,	60
24	Teakwood ventilators, glazed, complete	,,	12
25	Honey comb brick work	,,	27
26	Jack arched terraced roof complete	Sqr.	5·00
27	Roofing with old Mangalore tiles and reepers complete ...	,,	4·93
28	Brick in mortar binding walls, over roof	Rft.	90
29	Flooring with first class Mangalore tiles on 3" concrete and cement pointing.	Sqr.	11·22
30	Silicate blue painting to doors and windows	,,	6·09
31	Plastering in mortar	,,	46·48
32	Whitewashing two coats	,,	46·48
33	Zinc water down pipes with fixtures	Rft.	70
34	Providing sinks in bath rooms	No.	2
35	Road forming and levelling grounds all over the building, and other unforeseen works.	L. S.	...

A. TANDONI RAO,
Executive Engineer.